



**POLYPROPYLENE ROOT BARRIER
ELEVATION**

NOTES:

1. Drawing in millimetres unless noted otherwise.
2. Root barrier to be installed where directed by the City of Port Phillip.
3. For existing tree, the soil area is to be excavated in accordance with AS4970 and best practice. Care should be taken with all construction equipment to prevent damage to existing trees.
4. Protection of tree roots should be to best practice standards and AS4970.
5. Where excavation will occur, contractor must conduct a Dial Before You Dig (www.1100.com.au).

A APPROVED FOR USE		DEC 2020
No	Revision	Date

Disclaimer:
The authors and sponsoring organisations shall have no liability or responsibility to the user or any other person or entity with respect to any liability, loss or damage caused or alleged to be caused, directly or indirectly, by the adoption and use of these Standard Drawings including, but not limited to, any interruption of service, loss of business or anticipatory profits, or consequential damages resulting from the use of these Standard Drawings. Persons must not rely on these Standard Drawings as the equivalent of, or a substitute for, project-specific design and assessment by an appropriately qualified professional.



DRAWING NOT TO SCALE	
Approved	Project Services
Date	Dec. 2020

Drawing Title	TREE ROOT BARRIER
Original Size	A3
Drawing No:	CPP3412
Rev:	A