
Low Impact Development Consulting

CITY OF PORT PHILLIP
PORT PHILLIP PLANNING SCHEME

SECONDARY CONSENT APPROVAL under Condition No. 2 in Planning Permit No: 1051/2017/A

Date: 24/09/2024 Sheet: 1 of 22



Waste Management Plan

Mixed-use development (residential, hotel and restaurant) 28-32 Albert Rd, South Melbourne

Prepared for: DCF Developing Entity 28 Albert Road, South Melbourne Pty Ltd Prepared by: AV – Low Impact Development Consulting

DATE: 17/09/2024

- e: info@lidconsulting.com.au
- o: 03 9016 9486
- a: 6, 114 Flinders St, Melbourne 3000
- w: www.lidconsulting.com.au

Version: 1, Version Date: 14/05/2025

Waste Management Plan – 28-32 Albert Rd, South Melbourne

Version	Date	Description	Prepared by
1.0	16/04/2020	For Issue	VH
2.0	6/06/2022	Revised per drawings REV F	AV
3.0	19/12/2022	Revised per planning permit conditions dated 31 October 2022	AV
4.0	26/05/2023	Revised per condition 1 assessment	AV
5.0	9/08/2024	Revised per drawings REV P2	AV
5.1	17/09/2024	Updated number of apartments	AV

CITY OF PORT PHILLIP PORT PHILLIP PLANNING SCHEME

SECONDARY CONSENT APPROVAL under Condition No. 2 in Planning Permit No: 1051/2017/A Note: This approval relates to ther indicated/highlighted area(s) only

Date: 24/09/2024 Sheet: 2 of 22

Disclaimer

This report is copyright and has been written exclusively for the subject project discussed throughout. No part of this document may be reproduced or transcribed without the express agreement of LID Consulting Pty Ltd. The content of this report remains the intellectual property of LID Consulting.

The content of this document represents the entirety of work output or recommendations offered by LID Consulting for this particular project. This content supersedes all other verbal discussions undertaken by LID Consulting representatives in relation to this project.

Commercial waste calculations are based on rates provided by government organisations and adopted and used as an industry standard. Bin numbers and spatial requirements have been calculated in accordance with these guidelines. The end user requirements may vary from this depending on the business use, type and operational practice.

PORT PHILLIP PLANNING DEPARTMENT, Dage Received: 12 May 202

Waste Managemental Plean National Western Management of the Manage

Contents

Overview.....

SECONDARY CONSENT APPROVAL

under Condition No. 2 in Planning Permit No: 1051/2017/A
Note: This approval relates to ther indicated/highlighted area(s) only

	1.1	Waste Collection Summary	Date: 24/09/2024	Sheet: 3 of 22 1
		Development Summary		1
		Proposed Solution – Resider	ntial	2
		Proposed Solution - Comme	ercial	3
		Council Considerations		4
		Waste Links		5
2	Wo	aste Collection Details		5
	2.1	Garbage and Recycling Co	ollection	5
		Waste Management		5
		Bin Store Access		6
		Waste Vehicle Requiremen	ts	6
		Collection Times		6
		Internal Waste Manageme	nt	6
		Response to Increasing Rat	es of Waste Generation	7
		Soft Plastic Recycling		
	2.2	Organic Food Waste Recyc	cling	7
		Organic Food Waste Divers	ion Options	8
	2.3	Hard Waste Collection		8
	2.4	E-Waste Recycling		9
		Household Collection of E-V	Vaste	9
3	De	sign Inclusions		10
	3.1	Bin Store Design		10
	3.2	Traffic Management		10
	3.3	Litter Spread		10
	3.4	Noise Management		11
	3.5	Odour Reduction		11
	3.6	Signage, Education & Safe	'y	11
4	On	going Waste Management		12
5	Dis	claimer		13
App	oenc	dix 1 - Bin Collection Plan		14
Apr	oenc	dix 3 - Swept Paths		18

LID acknowledges and pays respect to the Australian Aboriginal and Torres Strait Islander people, to their ancestors and elders, past, present and emerging, as the traditional custodians of the lands upon which we work and live. We recognise Aboriginal and Torres Strait Islander people's deep cultural and spiritual relationships to the water, land and sea, and their rich contribution to society.

PORT PHILLIP PLANNING PEPAR LIVENT, Date Received: 12 Way 202

Waste MARGEMENLAR PLANNING SHEWEIDOURNE

SECONDARY CONSENT APPROVAL

under Condition No. 2 in Planning Permit No: 1051/2017/A Note: This approval relates to ther indicated/highlighted area(s) only

1 Overview

Low Impact Development (LID) Consulting was engaged by DGF Developing Entity 28, Albert Road, South Melbourne Pty Ltd to assess the proposed amendments to the development at 28-32 Albert Rd, South Melbourne and document a Waste Management Plan.

A waste management analysis has been undertaken based on the following documents:

- Sustainability Victoria Better Practice Guide for Waste Management and Recycling in Multi-Unit Developments 2018;
- 2. Port Phillip Council planning scheme clauses 19.03-5S and 58.06-3 (Standard D23)

This report is based on the drawing sets:

A02.01-A02.31 Rev. P2, received 11th of December 2023.

1.1 Waste Collection Summary

A private collection service is proposed to collect the residential $2 \times 660L$ garbage, $2 \times 660L$ comingled recycling bins, $2 \times 240L$ glass recycling bins and $3 \times 240L$ food organics and garden waste (FOGO) bins three times per week. The private waste contractor will also collect the commercial $5 \times 660L$ garbage bins, $2 \times 660L$ co-mingled recycling bins, $3 \times 240L$ glass recycling bins and $4 \times 240L$ food organics and garden waste (FOGO) bins five times per week.

Collection is to occur on the lower ground level (LG). The private collection contractor is responsible to transfer bins from the bin store located on the lower ground level, next to the loading bay. The waste vehicle will collect and empty bins onsite. The private collection contractor will be responsible for returning bins to the bin store and under the waste chutes immediately after collection has occurred.

The approved Waste Management Plan (WMP) will be the model to be adopted for this development. Detailed design and as-built installation must incorporate the design proposed and approved under this WMP. Any revisions of the WMP or changes to the approved waste system of the development may require Council approval and may require a re-submitted Waste Management Plan. More detail is contained within this report.

Development Summary

Address: 28-32 Albert Rd, South Melbourne

Type: Mixed use (residential apartments, hotel, restaurant and gym)

Dwellings: 44

Break up of units: 16 x 1 bed apartments

4 x 2 bed apartments 18 x 3 bed apartments 6 x 4 bed apartments

Commercial tenancy/ space: Qty/Area

Hotel (no. beds) 97
Hotel lobby 89m²
Restaurant & Cafe 392m²
Wellness/fitness centre 219.5m²

PORT PHILLIP PLANNING PEPAR LIVENT Date Received: 12 Way 202

Waste MARGEMENLING PLANNING SUFFICE IDOURNE

SECONDARY CONSENT APPROVAL

Sheet: 5 of 22

Bar under Condition No. 2 in Planning Permit No: 1051/2017/A
Office 26n Note: This approval relates to ther indicated/highlighted area(s) only

Refer to Appendix Diatesite44090202024an

Collection Type: Private collection service to collect all waste streams

Collection Location: On site

Site Layout:

Bin Store Location: Lower Ground Level

A private collection service using a mini rear loader will be used for collection. The site plan in **Appendix 1** shows the site area collection identified as a loading bay during off peak periods.

A small Mini Rear Loader vehicle (length 6.4m, 2.5m wide, 2.08m head clearance) has sufficient clearance required (ie. 2.4m in the loading bay) for the loading of bins, therefore onsite collection can occur.

Proposed Solution – Residential

Residential		nillip Council generation rates		Proposed Solution			
	No. All		Total estimated waste volume	No. of Bins	Bin Size	Collection Frequency	
General Waste (landfill)		Rates are per dwelling per week: 1 bed = 80L 2 beds = 100L 3+ beds = 120L	2964L to landfill	2	660L	Three times weekly	
Co- mingled Recycling	44	Rates are per dwelling per week: 1 bed = 80L 2 beds = 100L 3+ beds = 120L	3192L of recycling	2	660L	Three times weekly	
FOGO / Garden waste		35% of garbage waste rates ¹	1596L of food & garden organics	3	240L	Three times weekly	
Glass ²		30% of recycling waste rates	1368L of glass	2	240L	Three times weekly	
Hard Waste		2m ² provided	N/A	N/A	N/A	As required by a private contractor	

¹ Sustainability Victoria – Multi-unit and Commercial Development Waste and Recycling Generation Rates Calculator: https://calculators.sustainability.vic.gov.au/mud-waste-management/

² The Age (2019), https://www.theage.com.au/national/victoria/victorians-to-get-cash-for-bottles-scheme-20200224-p543ms.htm

PORT PHILLIP PLANNING PEPAR INFINIT DATE Received: 1							e Received: 12	way 2025
				Waste MARGERENIELLR - PLEANNIBLE RS, GHENTE Ibourne				
				SECO	NDARY COI	NSENT APPI	ROVAL	
Clothes / Charity Bin		N/A	N	N <i>µ</i> nder Condition ote: This approval	No. 2 _l in Plar relates to the	nning⊵₽⊛rmit r indicated/hi	Nas 1051i/201 ghlig bted are a private	7/A (s) only
				Date:	24/09/2024	Sheet:	6 6 р<u>и</u>т астог	

Proposed Solution - Commercial

	Port Phillip Cour Waste generation		Proposed solution			
Commercial	Allowances Total estimated was volume		No. of Bin Siz		Collection Frequency	
	Hotel: 5L/bed per day Hotel lobby:	Hotel: 5 x 97 x 7 = 3,395L per week Hotel lobby:				
	10L/100m ² per day	10 x 0.89 x 7 = 62L per week				
General	Restaurant & Cafe: 660L/100m ² per day (open 6 days)	Restaurant & Cafe: 660 x 3.92 x 6 = 15,523 per week	See See below		See below	
Waste (landfill)	Wellness/ fitness centre: 10L/100m² per day	Wellness/ fitness centre: 10 x 2.19 x 7 = 154L per week				
	Bar: 50L/100m² per day (open 6 days)	Bar: 50 x 1.45 x 6 = 435L per week				
	Office: 10L/100m² per day (open 7 days)	Office: 10 x 0.26 x 7 = 18L per week				
	TOTAL (excluding FOGO)	15,670 per week	5	660L	Five times a week by a private contractor	
Co-mingled Recycling	Hotel: 5L/bed per day	Hotel: 5 x 97 x 7 = 3,395L per week	See	See	See below	
and glass	Hotel lobby: 10L/100m² per day	Hotel lobby: 10 x 0.89 x 7 = 62L per week	below	below	Jee Delow	

PC	ORT PHILLIP PLANNING PEPAR LWENT Date Received: 12 Way 20	歹
	CH Y OF PORT PRILLIP	十

Waste Mangement Lind R - Pleas NAIL De Contra Commence

SECONDARY CONSENT APPROVAL

	<u> </u>				APPROVAL	
	Restaurant &					
	cafe:	200 Môtê2 This approval r	elates to the	er indicate	d/highlighted are	ea(s) only
	200L/100m ²	= 4.704L per week				
	per day (open	Date: 2	4/09/2024	Sh	eet: 7 of 22	
	6 days)					
	1A7 = 11	AAI - Hora (CO)				
	Wellness/	Wellness/ fitness centre:				1
	fitness centre:	10 x 2.19 x 7				
	10L/100m ² per	= 154L per week				1
	day	Port	.			1
	Bar: 501/100m ² por	Bar:				
	50L/100m ² per	50 x 1.45 x 6				
	day (open 6	= 435L per week				
	days)	Office:	.			
	Office:	Office:				
	10L/100m ² per	10 x 0.26 x 7				
	day (open 7	= 18L per week				
	days)				Fig. 1	
	TOTAL				Five times a	
	(excluding	6,138L per week	2	660L	week by a	
	glass)				private contractor	
	Included in	Glass assumed to			Confidence	
	above co-	equate to 30% of			Five times a	1
	mingled	recycling waste rates.			week by a	
Glass	recycling	100,0mig music luios.	3 2401		private	
	generation	2,630 L per week			contractor	1
	rates.	, poi moun			35	
	Included in	FOGO assumed to				
FOGO /	above	equate to 20% of			Five times a	1
•	general waste	recycling waste rates.		0.40:	week by a	1
Garden	(landfill)		4	240L	private	
waste	generation	3,917L per week			contractor	
	rates.					
		N/A	See			
		See Section 2.3 for Hard	Section		As required by	1
Hard Waste	NA	Waste Collection	2.3 for		a private	1
			more		contractor	
			detail			
		N/A	See		As often as	
		See Section 2.4 for E-	Section		required to	
E-waste	NA	Waste Recycling	2.4 for		the maintain	
			more		space	1
			detail		space	

Council Considerations

 Whilst Port Phillip Council does offer collection of larger bin sizes (ie. 660L and 1100L bins), it currently has a limit of one kerbside collection per week for business and commercial tenancies.

PORT PHILLIP PLANNING DEPARTMENT, Date Received: 12 Way 202:

Waste MARGEMENLAR PLANNING SHEWEIDOURNE

SECONDARY CONSENT APPROVAL

- Utilizing the Council collection serving is rob point in the property of the prop
- The private collection service is to occur with the 21409020024 ries and 5.11455 it 6015020 ing bay during off-peak periods. Off-peak periods have been identified as any time outside of 7-9am and 4-7pm on weekdays.
- Onsite collection is the most feasible. Swept paths have been provided (see Appendix 3) indicating that a Garwood mini rear-loader only is able to enter the site from Palmerston Crescent, traverse the rear laneway and enter the site in a forward direction. The waste vehicle will collect the waste from within the site, use the turntable to turnaround and exit the property in a forward direction.

Waste Links

City of Port Phillip Council Waste and Recycling Directory:

http://www.portphillip.vic.gov.au/waste-management.htm

Waste collection companies in Victoria:

- Waste Wise Environmental www.wastewise.com.au
- Kartaway http://www.kartaway.com.au/melbourne/index.html
- iDump Waste Management <u>www.idump.com.au</u>
- Wastech www.wastech.com.au
- Easy Waste http://www.easywaste.com.au
- Citywide www.citywide.com.au
- JJ Richards & Sons www.jjrichards.com.au
- Sita www.sita.com.au

2 Waste Collection Details

2.1 Garbage and Recycling Collection

Waste Management

- Residents will be required to cart their waste from the dwellings to the bin rooms located on
 each floor and dispose of waste streams accordingly. Garbage and co-mingled recycling
 excluding glass and FOGO can be disposed of via the waste chutes. Glass and FOGO are
 to be disposed of in the dedicated bins located in the bin room. Glass is not to be disposed
 of via the chute as they may break up on impact with the bin located on lower ground
 level.
- The Owner's Corporation and/or facilities manager will be responsible for transferring glass recycling and FOGO bins from each level to the lower ground bins in the bin store room as required.
- Similarly, large items such as cardboard boxes and hard waste will need to be disposed of
 directly in the bin store room located on lower ground. It is the resident's responsibility to
 appropriately dispose of these items to ensure the bin chutes do not get blocked up with
 large items.
- The Owner's Corporation and/or facilities manager will be responsible for monitoring and manually rotating residential bins located under the bin chutes as necessary. An empty 660L bin will need to be manoeuvred under the waste chute as the previous bin fills up.
- A sign is to be included within each level's bin chute room indicating that the garbage, comingled recycling, glass recycling and FOGO will not be available during waste collection time.

PORT PHILLIP PLANNING DEPARTMENT, Date Received: 12 Way 202:

Waste MORGERPHILLIP - 28-32 NIDHER & CHEME IDOURNE

SECONDARY CONSENT APPROVAL

Commercial tenancies and/or the indentenant of the indentenancies to the lower grouped things has proved the indentenancies to the lower grouped things has proved the indentenancies to the lower grouped things have been easily to the indentenancies to the lower grouped things have been easily to the indentenancies to the lower grouped things have been easily to the indentenancies to the lower grouped things have been easily to the indentenancies to the lower grouped things have been easily to the indentenancies to the lower grouped things have been easily to the indentenancies to the lower grouped things have been easily to the indentenancies to the lower grouped things have been easily to the indentenancies to the lower grouped things have been easily to the indentenancies to the lower grouped things have a lower grouped things have a lower grouped things have a lower grouped the indentenancies to the lower grouped things have a lower grouped the indentenancies to the lower grouped things have a lower grouped the indentenancies to the lower grouped things have a lower grouped the indentenancies to the lower grouped things have a lower grouped the indentenancies to the lower grouped the indentenancies the indentenancies that the indentenancies is a lower grouped the indentenancies that the indentenancies is a lower grouped the indentenancies to the lower grouped the indentenancies that the indentenancies is a lower grouped the indentenancies that the indentenancies is a lower grouped the indentenancies that the indentenancies is a lower grouped the indentenancies that the indentenancies is a lower grouped the indentenancies that the indentenancies is a lower grouped the indentenancies in the indentenancies is a lower grouped the indentenancies in the indentenancies in the indent

- The Owner's Corporation is responsible for all aspects of waste management including access for the waste contractor to enter the site and bin store on the days of collection.
- The private collection contractor will be responsible for transferring all residential and commercial bins from the bin store to the waste vehicle parked on the loading bay next to the bin store.
- Emptied bins will be returned to the bin store and placed under the residential bin chutes immediately after collection.

See **Section 4** for detail of Ongoing Waste Management.

Bin Store Access

- Manoeuvrability within the bin store area is generally open, with separate bin stores for the commercial and residential bins.
- Bin stores or bins should be vermin proof particularly where food waste is included. Ensure bin lids are closed and lockable if needed or the bin store is an enclosed space and considered to be largely vermin proof.

Waste Vehicle Requirements

- A Garwood mini rear-loader waste vehicle only is to enter the site from the rear laneway
 traverse towards the loading bay/waste collection area, retrieve, empty and return bins
 to/from the bin store, turn onsite using the turntable and exit the site in a forward direction
 onto the rear laneway.
- The loading bay has sufficient head clearance of greater than 2.4m required to load bins (see plans).
- The Owner's Corporation is responsible for ensuring the waste contactor has access to the site and bin store on the days of collection.
- A swept path for a mini-rear loader has been prepared and assessment included in Appendix 3.

Collection Times

Collection times Domestic waste – bin collection shall be in accordance with Council and EPA Noise Control Guidelines Publication 1254, which state:

 Collections of waste must not occur between 7am to 9am and 4pm to 7pm Monday to Friday.

Waste collections from private services are best suited on an alternate day to the Council service and completed at times of least interference/inconvenience to the local amenity and traffic conditions.

Internal Waste Management

• General landfill **garbage shall be placed in plastic bags** before placement into bins or in the bin chute.

PORT PHILLIP PLANNING DEPARTWENT, Date Received: 12 May 202

Waste MARGEMENLAR PLANNING SHEWEIDOURNE

SECONDARY CONSENT APPROVAL

- Recycling materials are not to be bagged and that the phop the path of the proposition of the bins. (Items in plastic bags in playse in the proposition of the page of the
 - Rigid plastic containers
 Date: 24/09/2024
 Sheet: 10 of 22
 - o Paper, cardboard
 - Glass bottles and jars
 - Steel cans, aluminium cans and aluminium foil are among items that can be recycled.
- But exclude:
 - Plastic bags
 - o Garden hoses
 - Rope (ropes and garden hoses can wrap around and damage equipment in the recycling plant).

For further detail of Ongoing Waste Management, please see Section 4.

Response to Increasing Rates of Waste Generation

- The total waste capacity exceeds the required allowance calculation by rounding up to the nearest bin size so there is built in capacity should waste levels increase beyond estimates.
- Garbage volumes can also be reduced if food waste and soft plastics are directed to recycling streams (see **Section 2.2** and **Soft Plastic** Recycling below).
- Should commercial glass recycling generation exceed that of co-mingled recycling, it may be appropriate to swap a co-mingled recycling bin for another glass bin.
- Should commercial garbage waste generation be lower than estimated, but recycling streams higher, then it may be appropriate to swap an 1100L garbage bin for an 1100L recycling bin.
- Where residential or commercial waste rates increase beyond the estimated volume, an additional 660L can be accommodated for within the bin store. The addition of this bin still maintains equal access to the commercial bins. Where waste continues to exceed the estimated rates, up to four additional 1100L bins can be accommodated for, however this would require rotation of the commercial bins to allow access to empty bins.

Soft Plastic Recycling

 Coles offer plastic bag and soft plastic recycling. Residents can take soft plastics and plastic bags to the supermarket for disposal. Any location identified on the Redcycle website http://www.redcycle.net.au/where-to-redcycle/.

2.2 Organic Food Waste Recycling

In Victoria, food and garden organics make up approximately 50 per cent of household garbage with food comprising on average 39 per cent (by weight)³. Food waste, when stuck in landfill is starved of air and rots and producing methane, 26 times more damaging than carbon dioxide. Diverting food waste from landfill is not only a really effective way to reduce greenhouse gas emissions, but also a regenerative solution, creating rich, healthy soil.

© Low Impact Development Consulting

³ Metropolitan Waste and Resource Recovery Group, Victoria State Government (2019), Introducing a kerbside food and garden organics collection service: A guide for local government < https://www.mwrrg.vic.gov.au/assets/resource-files/MWRRG-FOGO-Text-Interactive-20181119.pdf>

PORT PHILLIP PLANNING PEPARTWENT, Date Received: 12 May 202

Waste MARGEMENLAR PLANNING SHEWEIDOURNE

SECONDARY CONSENT APPROVAL

It is expected that organics collection will up the non-thing pollection will up the non-thing pollection will up the normal police of the included by the included with the i

Date: 24/09/2024 Sheet: 11 of 22

Organic Food Waste Diversion Options

- Sustainability Victoria provides information for households, schools and businesses alike to
 reduce food waste through their Love a List Challenge. Love Food Hate Waste aims to raise
 awareness of avoidable food waste from Victorian households. The average family in
 Victoria loses over \$2,000 a year from wasting food. And two thirds of it could have been
 eaten. https://www.sustainability.vic.gov.au/
- **Bokashi bins** http://www.bokashi.com.au/ are an effective way of reducing waste volumes and breaking down food waste for apartment dwellers. Food scraps are placed in bokashi bins with an accelerator mix added. The volume of waste food is reduced, and the waste in the bin is already on the path to being composted. Bokashi bins can be emptied into compost bins so providing a compost bin on site and having a garden also helps. Bokashi bins are also available from http://www.eco-organics.com.au/about-us.htm



Figure 1. Apartment Bokashi bin

2.3 Hard Waste Collection

- Hard rubbish collection is to be arranged with the Owner's corporation and collected by a
 private service as required to maintain the space. Residents and commercial tenants should
 liaise with body corporate to ensure hard waste collection occurs throughout the year.
- 5m2 have been provided for residential hard waste storage in the lower ground bin store.
- Alternatively, items can be taken directly to the Council local waste recovery centre located in South Melbourne:
 - o http://www.portphillip.vic.gov.au/tips.htm
- Unwanted bulky items, clothes and other consumables can be donated to charities, sold on online or at second-hand local market places as is if in good condition. If repair is required, seek out repair community centres for re-purposing. Search PlanetARK for a comprehensive listing to each council.
 - o https://recyclingnearyou.com.au/councils/
- Other sites that look to match unwanted items with new owners:
 - o https://au.ziilch.com
 - o https://www.freecycle.org
 - o https://www.ozrecycle.com
- In addition suppliers such as Ecycle http://www.ecyclesolutions.net.au will deliver whitegoods and either collect clean polystyrene from retailers or take polystyrene away after delivery.

PORT PHILLIP PLANNING DEPARTMENT, Date Received: 12 May 202

Waste MARGEMENIAR PLANNING SHEWEIDOURNE

SECONDARY CONSENT APPROVAL

under Condition No. 2 in Planning Permit No: 1051/2017/A

• TerraCycle is a national initional initional

o http://www.terracyclemap.com Date: 24/09/2024 Sheet: 12 of 22

2.4 E-Waste Recycling

As of 1st July 2019, there is a ban on e-waste to landfill in Victoria. Any item with a plug, battery or cord can no longer be placed in kerbside bins and instead must be deposited at a designated e-waste drop-off point. Electronic waste includes old mobile phones, computers, audio devices, refrigerators and other white goods, hair dryers, TVs, heaters, and air-conditioners.

Authorised electrical waste disposal locations can be found
 at https://recyclingnearyou.com.au/electrical. More details can also be found
 at https://www.sustainability.vic.gov.au/Campaigns/eWaste/Where-do-I-take-ewaste
 at https://www.mobilemuster.com.au

Household Collection of E-Waste

- One container with drawers or a number of small stackable plastic crates with minimum footprint 500x500mm are to be supplied to the development to collect e-waste recyclables such as:
 - o batteries
 - light globes
 - printer cartridges
 - o clothes.
- These items are to be recycled periodically as arranged by the Owners Corporation an as needs basis.
- Note in addition to Council recycling hubs and the e-waste links to over 1000 locations state-wide, Officeworks provide recycling drop-off points for printer cartridges, old IT equipment, and mobile phones.

© Low Impact Development Consulting

PORT PHILLIP PLANNING DEPARTMENT, Date Received: 12 Way 202:

Waste MARGEMENLING PLANNING SUFFICE IDOURNE

3 Design Inclusions

SECONDARY CONSENT APPROVAL under Condition No. 2 in Planning Permit No: 1051/2017/A Note: This approval relates to ther indicated/highlighted area(s) only

Date: 24/09/2024 Sheet: 13 of 22

3.1 Bin Store Design

Bin Store Design must include the following:

- A layout that allows access to all of the bins with adequate size to allow easy
 movement/transfer of the required number of bins. As residential bins will need to be moved
 to under the bin chute, equal access is not vital. Commercial bins currently have equal
 access to all bins.
- Hard rubbish area doors located in the lower ground bin store should be designed for easy access of larger hard waste.
- Floor and wall surfaces in the bin store area are to be appropriately durable and easily cleaned.
- Space suitable for bin wash down is to be available in the development. If this is the bin store then the floor is to be graded to a waste outlet with a litter trap. Alternately, a private contractor can be arranged to swap dirty bins for clean ones on a regular basis.
- If a bin wash is installed, a water tap and hose installed in or near the bin wash areas and correct drainage to sewer (never direct waste to storm water drains) should be designed in accordance with the relevant EPA Bunding Guidelines. Drains to the sewer to be located undercover to prevent rainwater infiltration.
- Ensure adequate lighting is provided in accordance with National Construction Code (NCC) guidelines.
- Meter boxes should not be included in bin store area.

3.2 Traffic Management

- Traffic management along Palmerston Crescent and Albert Road will not be an issue with collection occurring within the property boundary. As the waste vehicle will be parked in the loading bay, the internal driveway will also not be obstructed.
- Appropriate engineering standards will be addressed in the detailed design stage to ensure adequate pavement depths and clearance height.

3.3 Litter Spread

- Litter spread is to be managed by ensuring garbage and recycling bins are not overloaded, and lids are always closed.
- Litter spread is to be managed by the system of contractors collecting bins from within the property. As bins are not left outside overnight, the possibility of vandalism is removed.
- The private collection contractor's agreement should require their pickup of any waste that spills from the bins during collections.

PORT PHILLIP PLANING PEPARTWENT DATE RECEIVED: 12 May 2023

Waste MORGERPHILLIP - 28-32 NIDHER & CHEME IDOURNE

SECONDARY CONSENT APPROVAL

3.4 Noise Management

the hours of noise from collections.

under Condition No. 2 in Planning Permit No: 1051/2017/A Note: This approval relates to ther indicated/highlighted area(s) only Collections occurring during the stipulated collection timeframes (per Section 2.1) restricts

> Date: 24/09/2024 Sheet: 14 of 22

- Collection vehicles should not break up bottles at the point of collection, only once off site.
- Compaction of waste should only be carried out whilst waste vehicles are on the move.

3.5 Odour Reduction

- The bin store area and bins are to be monitored and cleaned on a regular basis to remove sources of smells.
- Mechanical ventilation (if proposed) will help to prevent odours from culminating in this area. Adnominally, the higher frequency of commercial waste will assist with removing sources of odour.

3.6 Signage, Education & Safety

It will be the responsibility of the Owner's Corporation to ensure all occupants have all of the material available to them and that they adhere to the required practices regarding waste management, sustainability and promoting waste minimisation.

- All education material will be in accordance with Council requirements.
- Instructional signage within shared communal bin stores is to indicate which bin and bin chutes is for garbage, co-mingled recyclables, glass and FOGO, and also include what items can be included in garbage and recycling bins, and items that need to be disposed of via other services.



Figure 2. Simple, brightly coloured signs, such as the example shown above, quickly communicate what items are acceptable for each bin.

A preliminary OHS risk assessment has been included to identify potential OHS issues, however this risk assessment does not replace the need for the Owners Corporation and collection contractors to complete their own OHS assessment for the bin collection process. See Appendix 2 for further detail.

PORT PHILLIP PLANNING PEPARTWENT, Date Received: 12 May 202

Waste MARGEMENLAR PLANNING SHEWEIDOURNE

SECONDARY CONSENT APPROVAL

A sign will be placed in the bin chuteler conditions Nio. taero Platoring Perthat Not to the total can be recycled at any local interior problem Relative to Website icated/highlighted area(s) only http://www.redcycle.net.au/where-to-redcycle/



Figure 3. A guick guide to some most commonly recycled Soft Plastic item

4 Ongoing Waste Management

The management and maintenance of the waste system will be the responsibility of the Owner's Corporation. Items to be addressed in maintaining the system include:

- The tenancy agreements are to outline a schedule of waste collection dates in accordance with the collection parameters outlined in **Section1.1** of this document.
- Ensuring the waste contractor has access to the loading bay and bin store on the days and time of collection and for also providing information to make building occupants aware that waste vehicles enter the site on lower ground level.
- Individual occupants and commercial tenants/staff and occupants are responsible for placing their waste in the appropriate bin or bin chute to ensure all waste types are collected and recycled where possible.
- That bins and bins stores are monitored regularly with bins rotated as required to ensure
 areas are fully operational with regular cleaning of the bins and bin store spaces and cleanup after collection if necessary. This includes rotating residential bins located under the bin
 chutes on lower ground.
- Management and coordination with the Owner's Corporation for hard waste collection.
- Provision of information to residents with guides of how to using the various bin systems. This
 includes (but not limited to) use of bin chutes, correct disposal of glass and FOGO, large
 items not to be disposed of via chutes, boxes to be flattened, containers for recycling
 washed and bins to not be over-full etc. See Section 3.6 for further information about
 Signage, Education & Safety.
- Monitoring and feedback to residents and commercial tenancies if the system is not working properly. Undertake a waste audit should it be suspected waste is not being placed in the correct bins.

PORT PHILLIP PLANKING DEPARTMENT, Date Received: 12 May 202

Waste MORGENEHILLIA - 26-30 NIDHERS GHENNEIDOURNE

5 Disclaimer

SECONDARY CONSENT APPROVAL

under Condition No. 2 in Planning Permit No: 1051/2017/A Note: This approval relates to ther indicated/highlighted area(s) only This report is written exclusively for the subject project discussed throughout. No part of this

document may be reproduced or to anscribed with put the angreement of the complete of the comp The content of this report remains the intellectual property of LID Consulting.

The content of this document represents the entirety of work output or recommendations offered by LID Consulting for this particular project. This content supersedes all other verbal discussions undertaken by LID Consulting representatives in relation to this project. If you have any questions in relation to items discussed with LID Consulting representatives or this report, please contact Craig Harris of LID Consulting.

Commercial waste calculations are based on rates provided by government organisations and adopted and used as an industry standard. Bin numbers and spatial requirements have been calculated in accordance with these guidelines. The end user requirements may vary from this depending on the business use, type and operational practice.

Waste Man BORNER HULL DE BLANGH RUGS SUH HENDE urne


SECONDARY CONSENT APPROVAL

under Condition No. 2 in Planning Permit No: 1051/2017/A Note: This approval relates to ther indicated/highlighted area(s) only

Date: 24/09/2024 Sheet: 17 of 22

Appendix 1 - Bin Collection Plan

See Appendix 3 for swept path assessment of the waste vehicle.



© Low Impact Development Consulting

PORT PHILLIP PLANNING DEPARTMENT, Date Received: 12 May 2021


Waste Man BORNER HULL DS BLANDAN RUGS SUPHINGUITNE


SECONDARY CONSENT APPROVAL

under Condition No. 2 in Planning Permit No: 1051/2017/A Note: This approval relates to ther indicated/highlighted area(s) only

Date: 24/09/2024 Sheet: 18 of 22

Bin store layout – Residential bins





PORT PHILLIP PLANNING PEPARTUENT Date Received: 12 Way 202

Waste Man BORTER HULL 128 B12 AI DON'T RUGS SUPHIENDEUrne

SECONDARY CONSENT APPROVAL

under Condition No. 2 in Planning Permit No: 1051/2017/A Note: This approval relates to ther indicated/highlighted area(s) only

Date: 24/09/2024 Sheet: 19 of 22

Bin store layout - Commercial bins



5 x 660L (0.85m(D) x 1.37m(W))
garbage bins collected 5 times weekly by
private contractor

2 x 660L (0.85m(D) x 1.37m(W))
co-mingled recycling bins collected 5 times
weekly by private contractor

3 x 240L (0.73m(D) x 0.58m(W))
glass bins collected 5 times weekly by
private contractor

4 x 240L (0.73m(D) x 0.58m(W))
FOGO bins collected 5 times weekly by
private contractor

PORT PHILLIP PLANNING DEPARTMENT, Date Received: 12 May 2021

Waste Man BORNE TO PHOLICE BLANDAN RIGSSON HEAVE Urne

Appendix 2 - Preliminary Risk Review

Class 1 Risk = Potential to cause death or permanent injury.

Class 2 Risk = Potential to compensation.

SECONDARY CONSENT APPROVAL

under Condition No. 2 in Planning Permit No: 1051/2017/A

Note: This approval relates to ther indicated/highlighted area(s) only Class 2 Risk = Potential to cause injury requiring Class 3 Risk = Potential to cause an injury

treatable with first aid. Sheet: 20 of 22

Activity	Steps involved in completing activity & risk	Risk level	Risk mitigating measures	Implementation responsibility
Moving of bins from bin store to collection space	Distance bins to be moved up the bin lift to the loading bay where the waste vehicle is parked.	2	Use max bin sizes of 660L. Minimise distance of travel, with the area kept free of all obstacles including loose gravel or dirt, steps, kerbs, speed bumps, berms, sills or ramps. Ensure all access points have suitably wide doorways and	Building Designer / Owners Corporation
			Circulation areas. Use the allocated bin lift appropriately. Ensure training is provided for the safe operation of the bin lift.	
Vehicle comes on site for collection	Large vehicle entering site, and reversing before exiting site. Major risk is hitting, particularly when reversing, young children, the elderly or unaware people	1	Vehicle driver entering site is to survey carpark for activity. If there is no activity near reversing location, driver to execute reverse move immediately before the situation can change. If there is activity, the driver should ensure the person/persons moving in the basement are aware of the pending reversing action, and have time to stay away from the reversing zone or ensure children are away from the reversing zone. Reversing should be at very slow speed. Reversing buzzers to be applied to all trucks.	Waste collection contractor / Owners Corporation
			The disabled carpark is allocated as a loading bay during off-peak periods. As collection is to occur during off-peak periods, there should be limited persons in the area. Signs indicating collection vehicles entering and exiting the site should be installed on basement level 1.	

PORT PHILLIP PLANNING DEPARTMENT Date Received: 12 May 202

Waste MARGEMENLAUR -PSANNINGRS, GOLFMENDOURNE


SECONDARY CONSENT APPROVAL

under Condition No. 2 in Planning Permit No: 1051/2017/A


Appendix 3 - Swept Paths This approval relates to ther indicated/highlighted area(s) only

Date: 24/09/2024 Sheet: 21 of 22

LOADING BAY AREA - INGRESS



LOADING BAY AREA - EGRESS




28-32 ALBERT ROAD, SOUTH MELBOURNE MIXED USE DEVELOPMENT

GENERAL NOTES:

BASE INFORMATION FROM: 17016_a0099.dwg,
17016_a0100.dwg & 17016_a0100LG.dwg
PREPARED BY Elenberg Fraser

FILE NAME: G28080-02 SHEET NO.: 02





PORT PHILLIP PLANING PEPARTWENT, Date Received: 12 May 202

SECONDARY CONSENTEARLE BOYA ISIMULATION

Width Front Track Rear Track

LEGEND

Sheet: 22 of 22

Waste Wise Mini (Hino 300)

Kerb to Kerb Radius

REAR WHEELS

1.44m 12.4m

- VEHICLE BODY - BODY CLEARANCE

PORT PHILLIP PLANTHINGESTRATIVE

under Condition No. 2 in Planning PermitoNose1@51k2017/A Note: This approval relates to ther indicated/highlighted area(s) only

Date: 24/09/2024

Traffix Group

Level 28, 459 Collins St, MELBOURNE VIC 3000 T: (03) 9822 2888 www.traffixgroup.com.au

REV DATE

26/05/22

NOTES

87A AMENDMENT

DESIGNED BY

J. YOUNG

CHECKED BY

L. FURNESS